



चुलाचुली गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



पत्र संख्या: ०८०१०८१

च.नं. ८९९



चुलाचुली, इलाम

कोशी प्रदेश, नेपाल
फोन नं-९७४६८७२४२५

प्रस्ताव पेश गर्ने सम्बन्धमा प्रथम पटक सूचना प्रकाशन मिति २०८०/०९/१६

प्रस्तुत विषयमा चुलाचुली गाउँपालिकाको वडा नं २ क्षेत्र अन्तर्गत मगर गाउँबाट नर्सरी जोड्ने बाटोको अपुरोलाई पूरा गर्ने लुज ग्राभेल (वडा न २), निगुरेहोली लुङ्गेली गाउँ देखी पूर्वजाने बाटो लुज ग्राभेल(वडा न २), मगर गाउँ बाट उत्तर पट्टि चेम्जोङ्ग मार्गबाट जनता मा.वि. जोड्नेबाटो लुज ग्राभेल (वडा न २), हस्त लावतीको घर देखि उत्तर पूर्वबाट हिमाली मार्ग जोड्ने सडक अधुरोलाई पूरा गर्ने(वडा न २), छवि ढकालको घर दक्षिण नर्सरी जोड्ने अधुरो बाटो पूरा गर्ने लुज ग्राभेल वडा नं २, अर्नाखाडी भक्त श्रेष्ठको घर उत्तर देखी पूर्व वडा नं. १ र २ को सिमाना मार्ग सम्म जोड्ने बाटो लुज ग्राभेल(वडा न २), खड्कुडे खोला देखी माझीको घर हुदै धन बहादुर राईको घर पश्चिम सम्मको बाटो लुज ग्राभेल(वडा न २)को निर्माण कार्य गर्नको लागि एकमुष्ट यस सूचना साथ सलग्न राखिएको BOQ बमोजिम के कति दररेटमा गर्न सकिने हो? तपशिल बमोजिमका कागजातहरु सहित मिति २०८०/०९/२३ गते कार्यालय समयभित्र चुलाचुली गाउँपालिकाको कार्यालयमा प्रस्ताव पेश गर्नुहुन यस गाउँपालिकाको मौजूदा सूचीमा सूचिकृत रहेका सम्पूर्ण निर्माण व्यावसायी/फर्महरुलाई सूचित गरिन्छ।

पेश भएको प्रस्तावहरुमध्ये प्रचलित सार्वजनिक खरिद ऐन २०६३ तथा सार्वजनिक खरिद नियमावली २०६४ बमोजिम न्यूनतम मुल्यांकित सारभुत रुपमा प्रभावग्राही प्रस्तावदातासंग सम्झौताको लागि प्रक्रिया अगाडी बढाइनेछ।

तपशिल :

१. रितपूर्वक भरिएको BOQ
२. कम्पनि दर्ताको प्रमाणपत्र
३. निर्माण व्यावसायी इजाजतको प्रतिलिपि
४. स्थायी लेखा नम्बर(प्यान) दर्ताको प्रतिलिपि
५. आ ब २०७९/८० को करचुक्ता प्रमाणपत्रको प्रतिलिपि

डिल्लीराम सुवेदी

प्रमुख प्रशासकीय अधिकृत

डिल्लीराम सुवेदी
प्रमुख प्रशासकीय अधिकृत

Chulachuli Rural Municipality
Office of Rural Municipale Executive
Chulachuli Ilam

Koshi Province Nepal


Name of Project: Ward no 2 Different Roads hume pipe and gravelling works
Location: Chulachuli-2, Ilam

Bill of Quantity(BOQ)

Pay Item No.	Description	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In Numbers	In Words		
	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications by mechanical means up to 30m lead	Sqm	3,210.00				
	Providing and laying River bed materials on prepared surface mixing without compaction loose gravelling	Cum	576.75				
	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer by mechanical means	Cum	148.95				
	Providing and laying of hand pack soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications	Cum	2.12				
	Providing and placing machine mixed cement concrete of M10 for the foundation and footing etc. including compaction, curing, testing etc all complete as per specification	Cum	1.41				
	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 600 mm internal dia. Pipe	R.m	5.00				
	Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 300 mm internal dia. Pipe	R.m	5.00				

87X



Providing and laying Reinforced cement concrete NP3 flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications having 900 mm internal dia. Pipe	Cum	5.00				
Providing and laying random rubble stone masonry work in cement sand mortar 1:6 in foundation complete as per Drawing and Technical Specifications	Cum	6.75				
Total Cost						
<u>VAT@13%</u>						
<u>Total Cost with VAT & P.S</u>						

2